BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/04/2019-20 Date: 12.06.2019

Indet No: BBMP/2018-19/OW/WORK_INDENT34929/CALL-2

SCHEDULE -B

Name of Work: Improvement of UGD (Under Ground Drainage) Lines in Jalahalli in ward no 16

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	700.67	Earthwork excavation by Manual means for foundaction of buildings, water supply, sanitary lines and electrical conduits etc., either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications	Cum	555.00	Rupees Five Hundred Fifty Five Only
2	705.00	Providing and laying in position to required level or slopem internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, tsting of pipes and joints, including cost of materials, labour charges complete as per specifications for 230mm dia	Rmtr	596.00	Rupees Five Hundred Ninety Six Only
3	13.00	Constructing brick masonry circular type manhole 1.22m internal dia at bottom 1.68m deep and 0.56m dia at top with table moulded non-modular bricks of class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3, finished with a floating cost of neat cement, foundation concrete M10 mix using 40mm and downsize granite metal and making necessary channel in cement concrete M 15 mix with 20mm and downsize granite metal finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560mm internal diametre confirming IS:12592, total weight cover and frame to be not less than 182kg, fixed in cement concrete 1:2:4, 20mm and downsize broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of mechineries complet as per specifications. (Excavation, footrests and 12mm thick cement plaster on the external surface shall be paid seperately). Specification for 1.68 m deep	Nos	32600.00	Rupees Thirty Two Thousand Six Hundred Only
4	634.50	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications allow 60% of rate considered under item	Cum	135.00	Rupees One Hundred Thirty Five Only
5	700.67	Lead charges for conveying the excavated earth including loading and unloading upto 15 kms as per directions	Cum	100.00	Rupees One Hundred Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner